

555 Oak Street East, North Bay, Ontario P1B 8L3 North Bay (Ontario) P1B 8L3 Telephone: (705) 472-4500 Téléphone: (705) 472-4500 Fax: (705) 476-5598

555, rue Oak est Télécopieur: (705) 467-5598

**ONR Signal Standards** Signal System Inspections & Tests (SSIT)

#### SSIT-1001(e)3 **Light Units - Alignment**

### **Purpose**

These instructions describe the light unit alignment and conspicuity tests required at grade crossing warning systems to ensure they are in good condition and properly aligned.

#### **Test Intervals**

Tests are performed when installed, as required, and at least once every twelve (12) months as prescribed in SSIT-7 Signal System Inspection and Test Intervals. Test must be performed on a clear day.

## Rail Safety

Employee shall ensure the site is safe for employees, the public, vehicular traffic and train operations as defined in SSIT-8 Protecting Train Operations prior to performing tests and inspections.

#### **Procedure**

The following tests are to be performed at each crossing warning system location:

Step	Procedure
Inspect Light     Units	<ul> <li>Inspection of lights shall be performed as outlined in SSIT-1001(b)1         Warning System Light Units &amp; Signs - Operation prior to performing alignment testing.</li> </ul>
Check Lamp     Voltage	<ul> <li>Lamp voltages shall be performed as outlined in SSIT-1001(e)1</li> <li>Lamp Voltage prior to performing alignment testing.</li> </ul>
3. Activate Warning System	<ul> <li>Open Test Switch.</li> <li>If crossing not activated: Protect crossing until resolved. Report to the ONR S&amp;C Supervisor. Record in site Log Book.</li> </ul>
4. Check Road Approach Lighting	<ul> <li>→ Check at least one set of front lights can be seen at all times on all road approaches.</li> <li>→ Check at least one set of front lights are aligned to 1.6m above the road surface through the center of the approaching traffic lane to the stopping distance.</li> <li>If flashing lights cannot be seen in approach: Adjust light angle to increase visibility. Contact the ONR S&amp;C Supervisor if you feel the lighting is not adequate along approach. Refer to Grade Crossing Standards Section 14 for alignment criteria.</li> </ul>
5. Check Stop Positions Lighting	<ul> <li>→ Check at least one set of front lights or back lights can be seen at all times while stopped at crossing.</li> <li>→ Check at least one set of back lights are aligned to 1.6m above the road surface at 15m in advance of warning signal.</li> <li>If flashing lights cannot be seen from stopped position: Adjust light angle to increase visibility. Contact the ONR S&amp;C Supervisor if you feel the lighting is not adequate along approach. Refer to Grade Crossing Standards Section 14 for alignment criteria.</li> </ul>

Continued on next page...



555 Oak Street East,

555, rue Oak est North Bay, Ontario P1B 8L3
Telephone: (705) 472-4500
Fax: (705) 476-5598
Télécopieur: (705) 467-5598

# **ONR Signal Standards** Signal System Inspections & Tests (SSIT)

Step	Procedure
6. Check Pedestrian Lighting	<ul> <li>→ Check light deflection can be seen from sidewalks or walkways.</li> <li>→ Check at least one set of lights are aligned to 1.6m above the road surface at 30m in advance of warning signal (or when first visible).</li> <li>If flashing lights cannot be seen by pedestrians: Adjust light angle to increase visibility. Contact the ONR S&amp;C Supervisor if you feel the lighting is not adequate along approach. Refer to Grade Crossing Standards Section 14 for alignment criteria.</li> </ul>
7. Check Lighting	<ul> <li>→ Check each pair of flashing lights emits same intensity.</li> <li>→ Check lights do not have dark spots or shadows.</li> <li>→ Check backlights are visible prior to front lights being out of field of vision.</li> <li>→ Check front lights' intensity reduces as back lights come into view.</li> <li>→ Check gate lights all emit same intensity.</li> </ul>
8. Restore Warning System	Close Test Switch.
9. Update Log Book	Add any notes of issues observed, or adjustments made.
10. Complete Test Form	<ul> <li>Record the test as completed on Grade Crossing Warning System Test Form.</li> <li>Record alignment changes on Light Unit Alignment Form (if applicable).</li> </ul>